Post-Commissioning Inspection

	POST-COMMISSIONING INSPECTION
	quality of construction and workmanship for the projects. This scope consists of an engineering design review, comprehensive visual and thermal inspection (including 100% of modules). HelioVolta uses a detailed checklist with 300+ points combined with a statistically significant sampling approach based on ISO 2859-1 to maximize findings and minimize risk.
BEST FOR	**substantial completion or final commissioning and are starting operations**. Focused on addressing quality-related items that would need to be addressed as part of the EPC punch list.
RESOURCES	Team of 1-2 Engineers for up to 1 day*
REPORTING	5 days from the inspection

DETAILED SCOPE OF WORK	POST-COMMISSIONING INSPECTION
Documentation review	*Full set*
Engineering drawings as-built review	*Full set*
System design and specifications match construction drawings	*Verification*
Commissioning documentation and testing results review	*Full set*
Data Acquisition System (DAS) installation and communication	*Inspection and Verification*
Visual Inspection: *Safety hazards, damage, bad practices, workmanship, code compliance, improper installation, abnormal conditions, misalignments, corrosion, labels, torque, improper operation, breakages, loose connections, water/moisture intrusion, positioning, bonding, grounding...*	
• *General site condition*	*100%*
• *Interconnection and metering*	*100%*
• *AC protections: AC disconnects and AC breakers*	*100%*
• *Inverters (central, microinverter or string)*	*100% Central / Sample ISO 2859 others*
• *Rapid shut down, optimizers, and other MLPE*	*Sample ISO 2859*
• *DC Distribution system and wire management*	*Sample ISO 2859*
• *Combiner Boxes (when applicable)*	*Sample ISO 2859*
• *Field-made connectors*	*Sample ISO 2859*
• *Factory-made connectors*	*Sample ISO 2859*
• *PV Modules*	*Sample ISO 2859*

© 2024 by HelioVolta LLC. All rights reserved.
Proprietary and confidential.

DETAILED SCOPE OF WORK	POST-COMMISSIONING INSPECTION
Thermal imaging: *Hot connections, outside temperature range, hot spots, temperature deltas, excessive temperatures…*	
• *AC protections and AC breakers, terminations*	
• *Inverters (central, microinverter or string)*	*100% Central / Sample ISO 2859 others*
• *Rapid shut down, optimizers, and other MLPE*	*Sample ISO 2859*
• *DC Distribution system, splices, junction boxes, and terminations*	*Sample ISO 2859*
• *Combiner Boxes, terminations*	*Sample ISO 2859*
• *Field-made connectors*	*Sample ISO 2859*
• *Factory-made connectors*	*Sample ISO 2859*
• *PV Modules*	*Sample ISO 2859*
IV-Curve tracing – per string	*Review commissioning data*
ISC – VOC measurements – per string	*Review commissioning data*
Insulation resistance test – per string	*Review commissioning data*
Continuity testing	*Spot checks*
Punch list generation	*Included*

© 2024 by HelioVolta LLC. All rights reserved.
Proprietary and confidential.